



AIRPORT INFRASTRUCTURE
BOURNEMOUTH

CLIENT: **Bournemouth International Airport**

VALUE: **£6.98m**

DURATION: **17 weeks**

Tel. **01425 657767** Email: admin@earlcoate.co.uk

www.earlcoate.co.uk   



Scope of work:

The construction of taxiway and aeroplane stands, diversion of pumping main, new interceptor and penstock, new cellular soakaway, gatic slot drains, foundations to lighting towers and associated works.

Comprising:

- 15,450m² pavement quality concrete
- 2,800m³ cement bound granular material
- 7,000t tarmac resurfacing
- 5,000t Type 1 and 8,000t 6F2 fill material
- 170m 500mm diameter slot drain
- 4 foundations for lighting towers, reinforced, cast insitu
- 1,061m² cellular soakaway
- Diversion of pumping main for Departure Building
- Topsoil, planings and suitable excavated materials recycled
- Additional works including airside road, taxiway, resurfacing and vehicle check point.